




Albers Conical Equal Area Projection
North American Datum 1983 (NAD 83)
State and County boundary information derived from U.S. Census Bureau TIGER/Line data
Base topographic data derived from 1:100,000-scale U.S. Geological Survey National Map digital data, accessed 2009 at <http://dpoas.cr.usgs.gov/viewer/line>
Image base mosaic derived from 30-meter Landsat 5 Thematic Mapper, 2000-2001
The mosaic used to produce this map has been modified for publication purposes. The correct way to display this in ArcMap and other programs is as follows: Red, band 1; green, band 2; and blue, band 3.

Suggested citation:
Cole, C. J., Noble, S. M., Blauer, S. L., Friesen, B. A., and Bauer, M. A., 2010.
Landsat Thematic Mapper image mosaic of Colorado, U.S. Geological Survey Scientific Investigations Map 3101, scale 1:650,000, 1 sheet.

¹ Parallel Inc., P.O. Box 281149, Lakewood, CO 80228.
² USGS Rocky Mountain Geographic Science Center, P.O. Box 25040, MS 516, Denver, CO 80225

LANDSAT THEMATIC MAPPER IMAGE MOSAIC OF COLORADO

By
Christopher J. Cole,¹ Suzanne M. Noble,¹ Steven L. Blauer,² Beverly A. Friesen,² and Mark A. Bauer¹
2010



Image base by C.J. Cole and S.M. Noble, 2009.
Digital cartography by C.J. Cole and M.A. Bauer.
Edited by L.A. Brink.
Publishing support provided by:
Denver Publishing Service Center
Map data supplied by U.S. Geological Survey, December 10, 2009.
For more information concerning this publication, contact:
USGS Rocky Mountain Geographic Science Center
Denver, CO 80225
1-888-455-6855
1-800-360-4800
Or visit the Rocky Mountain Geographic Science Center Web site at:
<http://rmgs.cr.usgs.gov>
For sale to U.S. Geological Survey Information Services
Box 2028, Federal Center, Denver, CO 80225
1-888-455-6855
This and other USGS products are available on the World Wide Web at <http://store.usgs.gov/>.
This report is available at: <http://dx.doi.org/10.3133/SI3101>
Any use of trade, product, or firm names is for descriptive purposes only and does not imply endorsement by the U.S. Government.
Although this information product, for the most part, is in the public domain, it also contains copyrighted material by the U.S. Government. Permission to reproduce copyrighted items for other than personal use must be secured from the copyright owner.

INTRODUCTION

The U.S. Geological Survey (USGS) Rocky Mountain Geographic Science Center (RMGSC) produced a seamless, cloud-minimized remotely-sensed image spanning the State of Colorado. Multiple enhanced Landsat 5 Thematic Mapper (TM) scenes collected during 2000-2008 were spectrally normalized via reflectance transformation and linear regression based upon pseudo-invariant features (PIFs) following the removal of clouds. Individual Landsat scenes were then mosaicked to form a six-band image composite spanning the visible to shortwave infrared spectrum. This image mosaic, presented here, will also be used to create a conifer health classification for Colorado in USGS Scientific Investigations Map 3103.
An archive of past and current Landsat imagery exists and is available to the scientific community (<http://glovis.usgs.gov/>), but significant pre-processing was required to produce a statewide mosaic from this information. Much of the data contained perennial cloud cover that complicated analysis and classification efforts. Existing Landsat mosaic products, typically three band image composites, did not include the full suite of multispectral information necessary to produce this assessment, and were derived using data collected in 2001 or earlier.

METHODS

Thirty orthorectified 30-meter Landsat 5 Thematic Mapper (TM) scenes (U.S. Geological Survey, 2009) were used to generate the mosaic for Colorado (Fig. 1, table 1). Landsat blue (band 1), green (band 2), red (band 3), near infrared (band 4), and shortwave infrared spectral information (bands 5 and 7) were used to produce this mosaic. Thermal infrared (band 6) was excluded from this mosaic, due to its 60-meter spatial resolution. The collection date of the Landsat scenes ranged from 2006-2008, with the majority being collected in 2008 (table 1). All Landsat scenes were converted to at-sensor reflectance, to reduce inter-scene variability that was due to differences in solar elevation angle and acquisition date (Huang and others, 2002). Areas affected by clouds in the base imagery were identified as data "gaps." Landsat scenes which were not cloud-affected in these areas were then selected and subset to "fill" these data gaps. Whenever possible, the "fill" scenes were collected in 2008. In cases where no such data existed, imagery from 2006-2007 was used. Landsat "fill" data were then normalized to the base imagery via linear regression based upon pseudo-invariant features that are spectrally consistent, and should not appreciably change by scene date (Hadjimimis and others, 2009; Schott and others, 1988). The normalized, reflectance image was then processed using ERDAS IMAGINE image processing software (ERDAS, 2009).

SUMMARY

A six-band image mosaic covering Colorado was produced. This mosaic includes blue (band 1), green (band 2), red (band 3), near infrared (band 4), and shortwave infrared information (bands 5 and 7). The image composite shown here displays three of the Landsat bands (1, 4, and 5), which are sensitive to the shortwave infrared, near infrared, and green ranges of the electromagnetic spectrum. Vegetation appears green in this image, while water looks black, and urban/developed areas appear pink. The explanation shows some generalized land cover features.
The Landsat mosaic used to produce this map has been modified for publication purposes. IMAGINE software (ERDAS, 2009) was used to apply a standard deviation stretch to increase scene contrast and enhance image interpretation.

REFERENCES CITED

Earth Resources Data Analysis System (ERDAS), 2009. ERDAS IMAGINE: Atlanta, ERDAS, Inc., Fuzhou Group, Sweden (available at: <http://www.erdas.com/>).
Hadjimimis, D.G., Clayton, C.R.L., and Retalls, Adriano, 2009. The use of selected pseudo-invariant targets for the application of atmospheric correction in multi-temporal studies using satellite remotely sensed imagery. International Journal of Applied Earth Observation and Geoinformation v. 11(1), p. 192-200.
Huang, Chongqun, Wylie, Bruce, Ying, Limin, Homer, Collin, and Zylstra, Gregory, 2002. Derivation of a tasseled cap transformation based on Landsat 7 at-satellite reflectance: International Journal of Remote Sensing v. 23(8), p. 1741-1748.
Schott, J.R., Salvaggio, Carl, and Woldosch, W.J., 1988. Radiometric scene normalization using pseudo-invariant features. Remote Sensing of Environment v. 26, p. 1-16.
U.S. Census Bureau, 2009. TIGER/Line Shapefiles: U.S. Census Bureau, accessed Nov. 3, 2009 at <http://www.census.gov/geos/www/tiger/tghp2009/tghp2009.html>.
U.S. Geological Survey, Earth Resources Observation and Science Center (EROS), 2009. U.S. Geological Survey Global Visualization Viewer: U.S. Geological Survey, accessed June 30, 2009 at <http://glovis.usgs.gov/BrowseViewer.shtml>.




Figure 1. Index map showing Landsat 5 Thematic Mapper coverage for Colorado, WRS-2 (Worldwide Reference System 2). Numbers refer to the path and row of the scene, and red lines indicate extent of the scene. Scenes overlap. Scenes may be obtained from U.S. Geological Survey Earth Resources Observation Science Center (EROS), at <http://glovis.usgs.gov/> (U.S. Geological Survey, 2009).

Table 1. Landsat scenes used to derive mosaic.
(Scenes were obtained from U.S. Geological Survey Earth Resources Observation and Science Center (EROS), available at: <http://glovis.usgs.gov/> (U.S. Geological Survey, 2009).)

Scene Identifier	Path/Row	Image Date
LT50110320062743EDC00	31/33	September 30, 2008
LT5011042006162EDC00	31/34	June 16, 2008
LT50132032006201EDC00	32/32	July 19, 2008
LT50132032007230EDC00	32/33	August 18, 2007
LT50132034006281EDC00	32/34	October 7, 2008
LT50132032006224EDC00	33/32	August 11, 2008
LT50132032006240EDC00	33/32	August 27, 2008
LT50132032006242EDC00	33/33	August 11, 2008
LT50132032006240EDC00	33/33	August 27, 2008
LT50132034007237EDC00	33/34	August 25, 2007
LT50132034008192EDC00	33/34	July 16, 2008
LT50132034008224EDC00	33/34	August 11, 2008
LT50140322006209EDC00	34/32	July 28, 2006
LT50140322006241EDC00	34/32	August 29, 2006
LT50140322007212EDC00	34/32	July 15, 2007
LT50140322006241EDC00	34/33	August 29, 2006
LT50140322007196EDC00	34/33	July 15, 2007
LT50140322007228EDC00	34/33	August 16, 2007
LT50140322006215EDC00	34/33	August 2, 2008
LT50140322006193EDC00	34/34	July 12, 2006
LT50140322006241EDC00	34/34	August 29, 2006
LT50140322007196EDC00	34/34	July 15, 2007
LT50140322006215EDC00	34/34	August 2, 2008
LT50150322007251EDC00	35/32	September 8, 2007
LT50150322006230EDC00	35/32	August 25, 2008
LT50150322007251EDC00	35/33	August 23, 2007
LT50150322006190EDC00	35/33	July 8, 2008
LT50150322006230EDC00	35/33	August 25, 2008
LT50150324007251EDC00	35/34	September 8, 2007
LT50150324006206EDC00	35/34	July 24, 2008
LT50160322006197EDC00	36/32	July 15, 2008
LT50160322006213EDC00	36/33	July 31, 2008




Figure 2. Index map showing Colorado and its counties. Derived from U.S. Census Bureau TIGER/Line data available at: <http://www.census.gov/geos/www/tiger/tghp2009/tghp2009.html> (U.S. Census Bureau, 2009).